

Addendum #1 for Delano High School and Valley High School Roofing Projects

This Addendum supplements, modifies changes, deletes from, or adds to the original bid documents for the project noted above and is hereby made a part of the proposal documents and any resulting contract documents.

Clarification: These projects are two separate bids; all bid documents can be found on the school's website under the maintenance tab.

- a. Address for bid drop off is: 1747 Princeton St. Delano, CA 93215
 - b. Bid due date/time is September 3rd, 2024 @ 2:00 PM.
 - c. You must be a pre-approved vendor for the district, this must be completed through Qualitybidders.com
2. Room 17 at Valley High School does not need gutters replaced.
3. 1/4" DensDeck is to be used on all roofs in lieu of 1/2".
4. On the MPR building at Valley High School, all angle irons on wind screen/privacy walls that would penetrate the roof line if left alone are to be cut to leave a flush surface that can be mounted to the roof in the same fashion. (see picture below)
 - a. If the bolts are rusted and have lost integrity replace them with a slightly thicker version of the same length and seated in a bed of Dymonic-100 both underneath and on top.



Addendum #1 for Delano High School and Valley High School Roofing Projects

5. All wooden conduit blocks are to be replaced with DuraBlocks.
6. The units on the MPR building at Valley High School are to be sat back down on the roof as they currently are, add a slip sheet of either walkpad or more single ply under the angle iron before setting back down to add further protection to the single ply.
7. Delano Joint Union High School will handle all junction boxes and electrical brackets that need to be lifted/moved.
8. On the MPR building of Valley High School, follow the below diagram for the walkpads, fully surround the roof hatch and lead to the wind/privacy wall entrances.

